Г		MEMBER SCHEDULE					
	MEMBER	DESCRIPTION				UMIN SCHEDULE	
	WP1	WALL PLATE: 90X45MGP10 H3; BOLTED TO	BRICK WALL BY	MEMBER	MEMBER SIZE	BOTTOM FIX	TOP FIX
-	D1	M10@900 RAFTER: 240X45@900 HVSPA	N				
-	R1 R2	RAFTER: 240745@300 MCP1	0	SC1	100 X 9 SHS	REFER FOOTING DETAIL F3	FULLY WELD TO PORTAL
	R3	RAFTER: 140X45@900 MGP1	0				FRAME BEAM ABOVE
-	RB1	ROOF BEAM: 240x36 HYSPAN	1	SC2	150 X 50 X 4 RHS	FULLY WELDED TO 250 X 150 X 10 PL BOLTED TO CONCRETE	6 SEAL PLATE + 8 CLEAT PLATE; 2M12 TO ROOF MEMBER
_	RB2	RIDGE BEAM; 180UB18.1				SLAB VIA 4 M10	
-	RB3 (PORTAL FRAME) RB4	RHS 200X100X8 STRUTTING BEAM; 300X63 LVL	.15	SC3	150 X 50 X 4 RHS	FULLY WELDED TO 250 X 150 X 10 PL BOLTED TO CONCRETE SLAB VIA 4 M10	6 SEAL PLATE + 8 CLEAT PLATE; 2M12 TO ROOF MEMBER
	RB5	STRUTTING BEAM; 240X63 LVL	.15				
	RB6	230PFC		SC4	89 X 3.5 SHS	FULLY WELDED TO 200 SQ X 10 PL BOLTED TO CONCRETE SLAB VIA 4M10	6 SEAL PLATE + 8 CLEAT PLATE; 2M12 TO ROOF MEMBER
				SC5	89 X 3.5 SHS	FULLY WELDED TO 200 SQ X 10 PL BOLTED TO CONCRETE SLAB VIA 4M10	REFER DETAIL 1
				SC6	89 X 3.5 SHS	FULLY WELDED TO 200 SQ X 10 PL BOLTED TO CONCRETE SLAB VIA 4M10	REFER DETAIL 1
		SF5		TD	R10 GALVANIZED TIE DOWN ROD; REFER TIE DOWN DETAILS/NOTES FOR MORE INFORMATION.	EMBED BOTTOM 100mm INTO SLAB, 50mm COG.	SITE WELD TO STEAL BEAM / LINTEL OVER. FOR TIMBER BEAMS / LINTELS; FULLY WELD TO 8PL AND FIX TO THE BEAM / LINTEL OVER VIA 2M10 BOLTS.
REFER TO STAIRS DETAIL	SF5 RE	ST1	SF5 RE	SF4		,	
SF1	STI]	STI		F	3	ST3
	RE SF2 ST2	ST1 FFL= 0C					
F1 SF3 SF2	SF2	F2	F1	<u>4^{C1}</u>		<u></u>	RE
				SF4	FS	SF4	
	F1	SF3	L p_				
FFL=-1C	SF3						SEA
F1		HARDSTAND TO BUILDERS SPEC			*		
SF3		Ll	F1)-	
F1			1'1		\checkmark	,	
					NI		
		FOOTING A	AND GROU	ND SLAB	IN PLAN		
		SCALE - 1 : 100					

	FOOTING SCH	IEDULE
	DIMENSIONS	REINFORCEMENT
F1	1000 X 1300 X 400 DEEP	N12 @ 200 EACH WAY,BTM
F2	1300 X 1300 X 400 DEEP	N12 @ 200 EACH WAY,BTM
F3	600DIA X 900 DEEP	REFER FOOTING DETAIL
SL		SQUARE MESH; D500L TO AS/NZS 4671
ТМ		TRENCH MESH; D500L TO AS/NZS 4671

GROUND SLAB NOTES:

REFER TO ROOF PLANS AND TIE DOWN DETAILS FOR COLUMNS ABOVE AND ANCHORED RODS LOCATIONS (TD).

RE: 3-L11TM;TIED TO SLAB REINFORCEMENT; L=2m @ ALL RE-ENTRANT/INTERNAL CORNERS AND AS SHOWN.



-		
A	27.10.16	ISSUED FOR REVIEW NOT CONSTRUCTION
Rev.	DATE	DESCRIPTION
CLIE ADD	NT: RESS:	
DRA	WING T	ITLE: STRUCTURAL
ENG	INEERIN	
JOR	NUMBE	R: GR218
	SHE	ET- 1 OF 12
D	RAWN:RS JOH N	CHECKED:R.S. SCALE:Shown N REZA SHIRAZ JER MIEAust 4051420 🍖
$\langle \mathcal{G} \rangle$	RIEN	GRIEng Consulting www.GRIEng.com Ph. 08 6262 8238 1Wexford St. Subiaco ABN 65 424 055 048

31.10.16 ISSUED FOR CONSTRUCTION

ISSUED FOR REVIEW NOT CONSTRUCTION

0

В

31.10.16



SF1 - FOOTING UNDER EXTERNAL WALLS

- CONFIRM EXACT LOCATION AND EXTENT WITH ARCHs DRGs.



SF2 - INDOOR/GARAGE FOOTING DETAIL SCALE - 1 : 20



(ST2) WET AREA STEP DOWN

- NOTES
- 1. SLAB REINFORCEMENT: SL82
- 2. FOR SLABS WITH BRITTLE OR EXPOSED CONCRETE FINISHES REFER TO THE ENGINEER.



SF3 - EXTERNAL GARAGE FOOTING DETAIL

0	31.10.16	ISSUED FOR CONSTRUCTION
В	31.10.16	ISSUED FOR REVIEW NOT CONSTRUCTION
А	27.10.16	ISSUED FOR REVIEW NOT CONSTRUCTION
Rev.	DATE	DESCRIPTION
CLIE ADD DRA ENG JOB	NT: PRESS: WING T INEERII NUMBI	TTLE: STRUCTURAL NG ER: GR218
	SH	EET- 2 OF 12
D	RAWN:RS JOH	CHECKED:R.S. SCALE:Shown IN REZA SHIRAZ NER MIEAust 4051420
$\langle \mathcal{G} $	RIEN	GRIEng Consulting www.GRIEng.com Ph. 08 6262 8238 1Wexford St. Subiaco ABN 65 424 055 048





- CONFIRM EXACT LOCATION AND EXTENT WITH ARCHs DRGs.



SF5 - FOOTING UNDER EXTERNAL WALLS

- CONFIRM EXACT LOCATION AND EXTENT WITH ARCHs DRGs.



- REFER TO ARCH'L DRG'S FOR EXACT NUMBER OF TREADS AND RISER AND FOR EXACT DIMENSIONS TO STEPS.



	0	31.10.16	ISSUED FOR CONSTRUCTION
- GROUND SLAB REO	В	31.10.16	ISSUED FOR REVIEW NOT CONSTRUCTION
	A	27.10.16	ISSUED FOR REVIEW NOT CONSTRUCTION
	Rev.	DATE	DESCRIPTION
OVER; REFER ORE INFO	CLIE ADD DRA ENG JOB	NT: DRESS: WING T INEERII NUMB	TTLE: STRUCTURAL NG ER: GR218
		SHI	EET- 3 OF 12
	D	RAWN:RS JOI	CHECKED:R.S. SCALE:Shown IN REZA SHIRAZ NER MIEAust 4051420 🚖
	$\widehat{\mathcal{G}}$	RIEC	GRIEng Consulting www.GRIEng.com Ph. 08 6262 8238

GR

1Wexford St. Subiaco

ABN 65 424 055 048

		MEMBER SCHEDULE		<u></u>		
	MEMBER	DESCRIPTION			LOIMIN SCHEDULE	
	WP1	WALL PLATE: 90X45MGP10 H3; BOLTED TO BRICK WALL BY M10@900	MEMBER	MEMBER SIZE	BOTTOM FIX	TOP FIX
	R1	RAFTER: 240X45@900 HYSPAN				EULLY WELD TO DODTAL
	R2	RAFTER; 140X45@900 MGP10	SC1	100 X 9 SHS	REFER FOOTING DETAIL F3	FOLLT WELD TO PORTAL FRAME BEAM ABOVE
	R3	RAFTER; 140X45@900 MGP10				
	RB1	ROOF BEAM: 240x36 HYSPAN	SC2	150 X 50 X 4 RHS	FULLY WELDED TO 250 X 150 X 10 PL BOLTED TO CONCRETE SLAB VIA 4 M10	6 SEAL PLATE + 8 CLEAT PLATE; 2M12 TO ROOF MEMBER
	RB2	RIDGE BEAM; 180UB18.1				
	RB3 (PORTAL FRAME)	RHS 200X100X8	SC3	150 X 50 X 4 RHS	10 PL BOLTED TO CONCRETE SLAB VIA 4 M10	6 SEAL PLATE + 8 CLEAT PLATE; 2M12 TO ROOF MEMBER
	RB4 RB5	STRUTTING BEAM; 300X03 LVL15 STRUTTING BFAM: 240X63 LVL15			SEID VII 4 MIO	
	RB6	230PFC	SC4	89 X 3.5 SHS	FULLY WELDED TO 200 SQ X 10 PL BOLTED TO CONCRETE SLAB VIA 4M10	6 SEAL PLATE + 8 CLEAT PLATE; 2M12 TO ROOF MEMBER
			SC5	89 X 3.5 SHS	FULLY WELDED TO 200 SQ X 10 PL BOLTED TO CONCRETE SLAB VIA 4M10	REFER DETAIL 1
			SC6	89 X 3.5 SHS	FULLY WELDED TO 200 SQ X 10 PL BOLTED TO CONCRETE SLAB VIA 4M10	REFER DETAIL 1
			TD	R10 GALVANIZED TIE DOWN ROD; REFER TIE DOWN DETAILS/NOTES FOR MORE INFORMATION.	EMBED BOTTOM 100mm INTO SLAB, 50mm COG.	SITE WELD TO STEAL BEAM / LINTEL OVER. FOR TIMBER BEAMS / LINTELS; FULLY WELD TO 8PL AND FIX TO THE BEAM / LINTEL OVER VIA 2M10 BOLTS.
CONTRACTOR OF CO	te solution of the second seco	T SOFPTI STEP (SECTION C)				
The second secon				N)-	

FIRST FLOOR SLAB PLAN SCALE - 1 : 100 LEGEND

GROUND FLOOR LOAD BEARING WALLS

FIRST FLOOR LOAD BEARING WALLS $\equiv := := := :=$

3C THICK SLAB AREA

2C THICK SLAB AREA

20mm WET AREA SET DOWN; 152mm REDUCED SLAB THICKNESS





0	31.10.16	ISSUED FOR CONSTRUCTION	
В	31.10.16	ISSUED FOR REVIEW NOT CONSTRUCTION	
A	27.10.16	ISSUED FOR REVIEW NOT CONSTRUCTION	
Rev.	DATE	DESCRIPTION	
CLIENT: ADDRESS:			
DRAWING TITLE: STRUCTURAL			

JOB NUMBER: GR218 SHEET- 4 OF 12 DRAWN:RS CHECKED:R.S. SCALE:Shown JOHN REZA SHIRAZ NER MIEAust @ 4051420 \$

Eng

GR

GRIEng Consulting www.GRIEng.com Ph. 08 6262 8238 1Wexford St. Subiaco ABN 65 424 055 048



FIRST FLOOR SLAB BOTTOM REINFORCEMENT PLAN

CIE	MT.	
Rev.	DATE	DESCRIPTION
A	27.10.16	ISSUED FOR REVIEW NOT CONSTRUCTION
В	31.10.16	ISSUED FOR REVIEW NOT CONSTRUCTION
0	31.10.16	ISSUED FOR CONSTRUCTION

CLIENT:





FIRST FLOOR SLAB TOP REINFORCEMENT PLAN SCALE - 1 : 100

RE: 2N16-200X 2000LONG; RE-ENTRANT BAR; CENTRAL TO SLAB

REFER TO ROOF PLANS AND THE DOWN DETAILS FOR UPPER COLUMNS (SC) AND ANCHORED RODS (TD) LOCATIONS .

CLIE	NT:	
Rev.	DATE	DESCRIPTION
A	27.10.16	ISSUED FOR REVIEW NOT CONSTRUCTION
В	31.10.16	ISSUED FOR REVIEW NOT CONSTRUCTION
0	31.10.16	ISSUED FOR CONSTRUCTION

ENGINEERING JOB NUMBER: GR218 SHEET- 6 OF 12 DRAWN:RS CHECKED:R.S. SCALE:Shown JOHN REZA SHIRAZ NER MIEAUST 4051420 GRIEng Consulting www.GRIEng.com Ph. 08 6262 8238 1Wexford St. Subiaco ABN 65 424 055 048





TYPICAL BRICK TO SLAB DETAIL	
SCALE - 1 : 20	

TYPICAL SLAB DETAIL	
SCALE - 1 : 20	

0	31.10.16	ISSUED FOR CONSTRUCTION
В	31.10.16	ISSUED FOR REVIEW NOT CONSTRUCTION
A	27.10.16	ISSUED FOR REVIEW NOT CONSTRUCTION
Rev.	DATE	DESCRIPTION
CLIE ADD DRA ENG JOB	NT: RESS: WING I INEERII NUMBI	TITLE: STRUCTURAL NG ER: GR218
	SHI	EET- 7 OF 12
D	RAWN:RS JOF	CHECKED:R.S. SCALE:Shown IN REZA SHIRAZ NER MIEAust 4051420

	MEMDED	MEMBER SCHEDULE		CO	LUMN SCHEDULE	
	WENDER WD1	WALL PLATE: 90X45MGP10 H3; BOLTED TO BRICK WALL BY	MEMBER	MEMBER SIZE	BOTTOM FIX	TOP FIX
	R1	M10@900 RAFTER: 240X45@900 HYSPAN				
	R2	RAFTER; 140X45@900 MGP10	SC1	100 X 9 SHS	REFER FOOTING DETAIL F3	FULLY WELD TO PORTAL FRAME BEAM ABOVE
	R3	RAFTER; 140X45@900 MGP10				
	RB1	ROOF BEAM: 240x36 HYSPAN	SC2	150 X 50 X 4 RHS	FULLY WELDED TO 250 X 150 X 10 PL BOLTED TO CONCRETE SLAB VIA 4 M10	6 SEAL PLATE + 8 CLEAT PLATE; 2M12 TO ROOF MEMBER
	RB2	RIDGE BEAM; 180UB18.1				
	RB3 (PORTAL FRAME)	RHS 200X100X8	SC3	150 X 50 X 4 RHS	10 PL BOLTED TO CONCRETE	6 SEAL PLATE + 8 CLEAT PLATE; 2M12 TO ROOF MEMBER
	RB4	STRUTTING BEAM; 300X63 LVL15			SLAB VIA 4 M10	LMIL TO ROOT MEMBER
	RB5 RB6	230PFC			EULLY WELDED TO 200 SO V 10	
			SC4	89 X 3.5 SHS	PULLY WELDED TO 200 SQ X TO PL BOLTED TO CONCRETE SLAB VIA 4M10	6 SEAL PLATE + 8 CLEAT PLATE; 2M12 TO ROOF MEMBER
			SC5	89 X 3.5 SHS	FULLY WELDED TO 200 SQ X 10 PL BOLTED TO CONCRETE SLAB VIA 4M10	REFER DETAIL 1
			SC6	89 X 3.5 SHS	FULLY WELDED TO 200 SQ X 10 PL BOLTED TO CONCRETE SLAB VIA 4M10	REFER DETAIL 1
			TD	R10 GALVANIZED TIE DOWN ROD; REFER TIE DOWN DETAILS/NOTES FOR MORE INFORMATION.	EMBED BOTTOM 100mm INTO SLAB, 50mm COG.	SITE WELD TO STEAL BEAM / LINTEL OVER. FOR TIMBER BEAMS / LINTELS; FULLY WELD TO 8PL AND FIX TO THE BEAM / LINTEL OVER VIA 2M10 BOLTS.
A RB4						

RB6

දුරි

Z,----



0	31.10.16	ISSUED FOR CONSTRUCTION	
В	31.10.16	ISSUED FOR REVIEW NOT CONSTRUCTION	
A	27.10.16	ISSUED FOR REVIEW NOT CONSTRUCTION	
Rev.	DATE	DESCRIPTION	
CLIE	CLIENT:		

ADDRESS:

Rev.	DATE	DESCRIPTION
А	27.10.16	CONSTRUCTION
۸	27 10 16	ISSUED FOR REVIEW NOT
		CONSTRUCTION

A	27.10.16	ISSUED FOR REVIEW NO CONSTRUCTION
Rev.	DATE	DESCRIPTION
CLIE	NT:	

DRAWING TITLE: STRUCTURAL ENGINEERING

SHEET- 8 OF 12 DRAWN:RS CHECKED:R.S. SCALE:Shown

GRIEng Consulting www.GRIEng.com Ph. 08 6262 8238 1Wexford St. Subiaco ABN 65 424 055 048

JOHN REZA SHIRAZ NER MIEAust

JOB NUMBER: GR218

Eng

CLIENT		
Rev.	DATE	DESCRIPTION
	27.10.10	CONSTRUCTION
Δ	27 10 16	ISSUED FOR REVIEW NOT
		CONSTRUCTION

		MEMBER SCHEDULE			COL	UMN SCHEDULE	
	MEMBER WP1	DESCRIPTION WALL PLATE: 90X45MGP10 H3; BOLTED TO BRICK WALL	BY	MEMBER	MEMBER SIZE	BOTTOM FIX	TOP FIX
	R1	M10@900 RAFTER: 240X45@900 HYSPAN					
	R2	RAFTER; 140X45@900 MGP10		SC1	100 X 9 SHS	REFER FOOTING DETAIL F3	FULLY WELD TO PORTAL FRAME BEAM ABOVE
	R3	RAFTER; 140X45@900 MGP10					
	RB1	ROOF BEAM: 240x36 HYSPAN		SC2	150 X 50 X 4 RHS	FULLY WELDED TO 250 X 150 X 10 PL BOLTED TO CONCRETE SLAB VIA 4 M10	6 SEAL PLATE + 8 CLEAT PLATE; 2M12 TO ROOF MEMBER
	RB2	RIDGE BEAM; 180UB18.1					
	RB3 (PORTAL FRAME) RB4	RHS 200X100X8 STRUTTING BEAM; 300X63 LVL15		SC3	150 X 50 X 4 RHS	FULLY WELDED TO 250 X 150 X 10 PL BOLTED TO CONCRETE SLAB VIA 4 M10	6 SEAL PLATE + 8 CLEAT PLATE; 2M12 TO ROOF MEMBER
	RB5	STRUTTING BEAM; 240X63 LVL15					
	RB6	230PFC		SC4	89 X 3.5 SHS	FULLY WELDED TO 200 SQ X 10 PL BOLTED TO CONCRETE SLAB VIA 4M10	6 SEAL PLATE + 8 CLEAT PLATE; 2M12 TO ROOF MEMBER
				SC5	89 X 3.5 SHS	FULLY WELDED TO 200 SQ X 10 PL BOLTED TO CONCRETE SLAB VIA 4M10	REFER DETAIL 1
				SC6	89 X 3.5 SHS	FULLY WELDED TO 200 SQ X 10 PL BOLTED TO CONCRETE SLAB VIA 4M10	REFER DETAIL 1
				TD	R10 GALVANIZED TIE DOWN ROD; REFER TIE DOWN DETAILS/NOTES FOR MORE INFORMATION.	EMBED BOTTOM 100mm INTO SLAB, 50mm COG.	SITE WELD TO STEAL BEAM / LINTEL OVER. FOR TIMBER BEAMS / LINTELS; FULLY WELD TO 8PL AND FIX TO THE BEAM / LINTEL OVER VIA 2M10 BOLTS.
		R3				N10-600Max; 1m LONG; LAID IN BED JOINTS; FULLY WELDED TO PORTAL FRAME (TYP.)	
<u>ج</u> ناب					ççî	*/	
		SUSPENDED SLAB		 	TATA A CARACTER A CARA	LISHWEI RB2	
		5 ⁰			Ser to		
					R2		
		86		ççî.	چ ا	> 	
ENDED		1					
SUSSLIB							
				_	\mathbf{A}	A	
			123]	_)	~
					\checkmark		
					NI		
					IN		



0	31.10.16	ISSUED FOR CONSTRUCTION	
В	31.10.16	ISSUED FOR REVIEW NOT CONSTRUCTION	
A	27.10.16	ISSUED FOR REVIEW NOT CONSTRUCTION	
Rev.	DATE	DESCRIPTION	
CLIE	CLIENT		

GR

ENGINEERING JOB NUMBER: GR218

I Eng

CLIENT:		
Rev.	DATE	DESCRIPTION
A	27.10.16	ISSUED FOR REVIEW NOT CONSTRUCTION
В	31.10.16	ISSUED FOR REVIEW NOT CONSTRUCTION

SHEET- 9 OF 12

DRAWN:RS CHECKED:R.S. SCALE:Shown JOHN REZA SHIRAZ NER MIEAust 4051420

GRIEng Consulting www.GRIEng.com Ph. 08 6262 8238 1Wexford St. Subiaco ABN 65 424 055 048

1.

- ROOF FRAMING TO BE RAFTERS@900 C/C MAX. RAFTERS/ PURLINS TO BE TIED DOWN BY PRYDA MULTI- GRIPS @ ALL 2. INTERSECTIONS UNO.
- 3.
- 2.
- INTERSECTIONS UNO. WALL PLATES (EXTERNAL/ INTERNAL) TO BE TIED DOWN AS SHOWN BELOW. LINTELS, TO BE TIED DOWN AS SHOWN BELOW. BEAMS SITTING ON OTHER BEAMS/ TOP PLATES TO BE TIED DOWN BY 1/30X1.0 TENSIONED STRAP RAPPED ROUND; FITMENT: 6X3.15x35 GALV. NAILS OR 4/12X16MM TEK SCREWS AT EACH END OF STRAP. (MAX SPAN=7M). UNDERPURLINS/RIDGE BEAMS/HIP RAFTERS TO BE TIED DOWN TO STRUTS@2 5MAX, AND CTULES TO WALL DIATES/STRUTTING DE AMO DY 4/20X4.0 3.
- 4. STRUTS@3.5MAX, AND STRUTS TO WALL PLATES/STRUTTING BEAMS BY 1/30X1.0 TENSIONED STRAPS @EACH STRUT END; FITTED BY 2/12x16mm TEK SCREWS AT EACH STRAP ENDS.
- EACH STRAP ENDS. TO TIE DOWN BEAMS ON INTERNAL WALLS USE 3.2mm, GRADE1570, WIRE ROPES AND CONNECTORS. THE ROPE TO BE LOOPED THROUGH A HOLE DRILLED 26C BELOW AND FITTED TO EITHER SIDES OF THE BEAM. ALL STRAPS/ ROPES TO BE TIGHT AND TENSIONED. 7.
- 8.





DOUBLE PRYDA MULTI GRIPS

30 x 0.8mm PGI GALVANISED STRAP AT 600c/c MAX. EMBEDDED INTO BRICKWORK 75mm MIN. TURN OVER WALL PLATE AS SHOWN & FIX TO PLATE WITH 2-12G TYPE 17 TEK SCREWS

ROOF TIE DOWN TO CAVITY MASONRY WALLS

SCALE 1:20

0	31.10.16	ISSUED FOR CONSTRUCTION
В	31.10.16	ISSUED FOR REVIEW NOT CONSTRUCTION
A	27.10.16	ISSUED FOR REVIEW NOT CONSTRUCTION
Rev.	DATE	DESCRIPTION
CLIE ADD DRA ENG JOB	NT: RESS: WING 1 INEERII NUMBI	TTLE: STRUCTURAL NG ER: GR218
	SH	EET- 11 OF 12
	RAWN:RS JOH	CHECKED:R.S. SCALE:Shown IN REZA SHIRAZ NER MIEAust 4051420 GRIEng Consulting www.GRIEng.com Ph. 08 6262 8238 1Wexford St. Subiaco ABN 65 424 055 048



- LINTEL TABLE NOTE:

 1.
 TO SUPPORT ROOF ABOVE WALL OPENING USE TABLE BELOW UNLESS NOTED OTHERWISE (UNO) ON LAYOUTS.

 2.
 LINTELS TO BE PROPPED AT LEAST 7 DAYS.

 3.
 AVOID LOADING LINTELS BY CONCENTRATED LOADS SUCH AS STRUTS, PROPS, BEAMS OR GIRDER TRUSSES OTHERWISE DEFENTED TO THE DUCUMENT

 REFER TO THE ENGINEER.
- AVOID LOADING LINTELS BY BRICK WALLS HIGHER THAN 4. 600mm. OTHERWISE, REFER TO THE ENGINEER.

	LINTEL TABLE				
BRICK WALL BEA	RING ROOF LOAD	BRICK WALL NOT B	EARING ROOF LOAD		
MAX. SPAN (mm) LINTEL		MAX. SPAN (mm)	LINTEL		
2200	90X90X6EA	3000	90X90X6EA		
2400	100X100X6EA	3350	100X100X6EA		
2550	100X100X8EA	3600	100X100X8EA		
3450	150X90X8UA	4200	150X90X8UA		
4000	150UB18.0				
4200	180UB22.2				
4600	T-BAR(T1); 200X10WEB 200X10 FLANGE				
5500	T-BAR (T2); 250X12WEB 200X10 FLANGE				



SCALE 1:20

0	51.10.10	ISSUED FOR CONSTRUCTION
В	31.10.16	ISSUED FOR REVIEW NOT CONSTRUCTION
A	27.10.16	ISSUED FOR REVIEW NOT CONSTRUCTION
Rev.	DATE	DESCRIPTION
CLIE ADD DRA ENG JOB	NT: RESS: WING 1 INEERII NUMBI	TITLE: STRUCTURAL NG ER: GR218
	SH	EET- 12 OF 12
	RAWN:RS JOH	CHECKED:R.S. SCALE:Shown IN REZA SHIRAZ NER MIEAust 4051420 Consulting Www.GRIEng.com Ph. 08 6262 8238 1Wexford St. Subiaco ABN 65 424 055 048

21 10 16

SITE PREPARATION

- 1. REMOVE TOPSOIL (ANY ORGANIC, LOOSE OR SOFT MATERIAL) AND ROOTS.
- 2. REFER TO THE REGARDING SITE CLASSIFICATION/PREPARATION REPORT FOR REQUIRED SAND PAD THICKNESS, SPECIFICATION AND CRITERIA.
- 3. THE SOIL AT BOTTOM LEVEL OF THE GROUND SLAB AND ALL FOOTINGS DOWN TO THE THICKNESS OF 750Min SHALL BE COMPACTED AND CERTIFIED BY THE ENGINEER.
- FOOTINGS SHALL BE LOCATED CENTRALLY BENEATH WALLS AND COLUMNS UNLESS NOTED OTHERWISE.
- 5. REFER TO SITE CLASSIFICATION/PREPARATION REPORT FOR MORE INFORMATION

DESIGN CRITERIA

- 1. BUILDING STRUCTURAL IMPORTANCE LEVEL 2.
- 2. WIND CLASSIFICATION: N2, WIND REGION A, TERRAIN CATEGORY 1.5, V_{hu} =40 m/s
- 3. ENVIRONMENT: MARINE, HIGH CORROSIVE
- 4. EARTHQUAKE:
- PROBABILITY FACTOR kp=1.0 HAZARD FACTOR Z<0.11
- SITE CLASS 'A' TO AS2870. ASSUMED BEARING PRESSURE MAX. 150 kPa, SUBJECT TO AVAILABILITY OF SOIL INVESTIGATION.
- 6. BUILDING IS DESIGNED FOR SHEET ROOF.

CONCRETE/REINFORCEMENT

- 1. FOOTING CONCRETE TO BE OF 32MPA GRADE; REINFO. COVER OF 70 (BOTTOM).
- 2. IN-DOOR GROUND SLAB CONCRETE COULD BE OF 25MPA GRADE WITH REINFORCEMENT COVER OF 25 (TOP) SHOULD DAMP PROOF MEMBRANE COMPLETELY PROTECT IT.
- 3. BEAMS CONCRETE TO BE OF 40MPA GRADE: REINFO. COVER OF 30 (INTERNAL) AND 45(EXTERNAL).
- 4. SUSP SLAB AND STAIRS CONCRETE TO BE OF 40MPA GRADE; REINFO. COVER OF 20 (INTERNAL) AND 45(EXTERNAL).
- 5. CAVITY FILL CONCRETE TO BE OF 32MPA GRADE; REINFO. COVER OF 20 .
- 6. IN DOOR COLUMNS CONCRETE TO BE OF 40MPA GRADE; REINFO. COVER OF 30 (UNO).
- 7. CONCRETE TO CONFORM WITH AS3600
- 8. ALL PROPS AND FORMWORK FOR BEAMS AND SLABS TO BE REMOVED BEFORE CONSTRUCTION OF ANY WALLS OR OTHER PERMANENT LOADING ON THE SLAB.
- 9. LAP ALL MESH AT LEAST ONE TRANSVERSE WIRE PLUS 25MM OR TO MANUFACTURER'S SPECIFICATION UNLESS OTHERWISE NOTED.
- 10. 0.2MM THICK WATERPROOF MEMBRANE TO BE PLACED UNDER ALL REINFORCED SLABS AND FOUNDATIONS. THE MEMBRANE TO BE LAPPED AND SEALED TO ENSURE MOISTURE BARRIER.
- 11. WHERE GROUT IS REQUIRED TO PROVIDE PROTECTION TO REINFORCEMENT, IT SHALL HAVE A GB OR GP CEMENT CONTENT OF NOT LESS THAN 300 Kg/m3
- 12. BLENDED CEMENT TO CONFORM WITH AS3972.
- 13. ALL CONCRETE IS OF 20 MAX AGG AND 80 SLUMP.
- 14. CONCRETE IS TO BE COMPACTED USING MECHANICAL VIBRATORS.
- SIZES OF CONCRETE ELEMENTS DO NOT INCLUDE THICKNESS OF APPLIED FINISHES.
 NO HOLES, CHASES OR EMBEDDED PIPES. OTHER THAN THOSE SHOWN ON THE STRUCTURAL
- NO HOLES, CHASES OR EMBEDDED PIPES, OTHER THAN THOSE SHOWN ON THE STRUCTURAL ENGINEER'S DRAWINGS, SHALL BE MADE WITHOUT THE APPROVAL OF THE ENGINEER.
- 17. CONCRETE SHALL BE CONTINUOUSLY WATER CURED FOR 3 DAYS AFTER POURING AND KEPT DAMP FOR NOT LESS THAN A FURTHER 4 DAYS THEREAFTER.
- 18. FORMWORK AND ITS REMOVAL TO BE IN ACCORDANCE WITH AS.3610
- 19. DO NOT USE ADMIXTURES TO CONCRETE UNLESS SPECIFIED OR PRIOR APPROVED BY THE ENGINEER.
- 20. CONSTRUCTION TOLERANCES TO BE IN ACCORDANCE WITH AS 3600 CL. 17.5.
- 21. SURFACE FINISHES TO BE IN ACCORDANCE WITH AS.3610.
- 22. CURING OF CONCRETE SHALL BE COMMENCED AS SOON AS POSSIBLE AFTER PLACING OR STRIPPING, REFER TO CLAUSE 19.1.5 AS 3600.
- 23. REINFORCEMENT SHALL COMPLY TO AS1302, A1303, AS1304 AS APPROPRIATE. LAPS SHALL BE IN ACCORDANCE WITH AS3600.
- 24. REINFORCEMENT SYMBOLS:-

N; NORMAL DUCTILITY GRADE 500N DEFORMED BARS TO AS 4671

- R; GRADE 230R HOT ROLLED PLAIN BARS TO AS 4671
- SL: HARD DRAWN REINFORCING FABRIC TO AS 4671
- W: HARD DRAWN PLAIN WIRE TO AS 4671
- 25. THE CONTRACTOR SHALL SUPPLY ALL NECESSARY BAR CHAIRS, SUPPORT AND SPACER BARS TO LOCATE REINFORCING STEEL IN ITS CORRECT LOCATION DURING CONCRETE PLACEMENT.
- ALL CAST IN FITTINGS SHALL BE STAINLESS STEEL OR HOT DIP GALVANISED AFTER FABRICATION (HDG900, 125MICOMILIMETER).
- 27. PROVIDE ALL EXPOSED EDGES AND CORNERS WITH 20 CHAMFERS OR FILLETS.
- REINFORCEMENT SHALL BE SPLICED WHERE SHOWN ON THE DRAWINGS. WHERE NOT DETAILED, SPLICES TO ALL REINFORCEMENT INCLUDING DISTRIBUTION BARS SHALL BE STAGGERED WITH MINIMUM OVERLAP OF 40 BAR DIAMETERS.
- 29. THE CORNERS OF ALL OPENINGS AND RE-ENTRANT CORNERS SHALL BE REINFORCED WITH 3-L11TM@TOP, 2000 LONG.
- 30. TEMPLATES SHALL BE USED TO CORRECTLY LOCATE AND HOLD IN POSITION HOLDING DOWN BOLTS DURING PLACEMENT OF CONCRETE.

FORMWORK

- 1. FORMWORK TO COMPLY WITH AS 3610.
- 2. BUILD ALL FORMWORK FROM ARCHITECTS DRAWINGS
- 3. MIN. STRIPPING TIMES
- WALLS/COLUMNS 3 DAYS UNO
- BEAMS/SLABS/STAIRS 14 DAYS UNO
- 4. BACK PROP SLABS AND BEAMS UNTIL CONCRETE STRENGTH IS F'c.
- 5. IF BRICKWORK IS TO BE BUILT ON SLAB, ALLOW CONCRETE TO REACH Fc, REMOVE ALL PROPS AND LOAD BRICKS ON SLAB TO ALLOW DEFLECTION TO OCCUR BEFORE BRICKWORK IS COMMENCED.

STEEL WORK

- 1. WORKS TO BE IN ACCORDANCE WITH AS4100 AND AS1554
- ALL STEEL SHALL BE IN ACCORDANCE WITH AS 3678, AS 3679 OR AS 1163. MINIMUM GRADE TO BE G300 FOR ROLLED SECTIONS AND PLATES, G350 FOR HOLLOW SECTIONS.
- 3. PROVIDE ALL CLEATS AND DRILL HOLES FOR FIXINGS WHETHER OR NOT DETAILED ON THE DRAWINGS TO THE APPROVAL OF THE STRUCTURAL ENGINEER. THIS INCLUDES ALL ARCHITECTURAL FIXINGS WHICH ARE NOT NECESSARILY SHOWN ON THE STRUCTURAL DRAWINGS.

HARDWOOD

@3.5MAX

ROLL OVER

LAYERS OF 'SUPER ALCOR'.

MORTAR CLASS SHALL BE M4 PER AS AS3700.

WELDED SIDE CLEAT AND 2-M16 BOLTS MIN.

LONGER LEG OF LINTELS TO BE VERTICAL

LINTELS TO BE IN ACCORDANCE WITH AS 3700 UNO.

AS1449/316L (UNS S31600 OR S31603 RESPECTIVELY).

BRICK WORK

2.

6.

10.

11.

12.

13.

16.

17.

18.

1.

2

3.

4.

CONCRETE GROUT.

CORPORATION APPROVAL.

(CAVITY) BRICKWORK RETAINING WALLS

CONCRETE WORK IS COMPLETE

SPECIFIED WIND REGION

2. METAL CLADDING TO BE STAINLESS STEEL.

CONSTRUCTION COMMENCEMENT.

BED JOINT.

ROOF/WALL CLADDING

DISCLAIMER

RETAINING WALLS

ROOF FRAMING (NOT TRUSS ROOF)

CLASS 4; IN ENCLOSED AND ABOVE GROUND LOCATIONS .

ROOF FRAME AS PER AS1684,2010 AND ENGINEERS DETAILS.

TIE DOWNS AS PER AS1684.2010 AND ENGINEERS DETAILS.

ROOF BATTENS MUST BE MINIMUM 70hX45w MPG10 PINE.

CLASS 2; IN EXPOSED LOCATIONS, BUT NOT IN CONTACT WITH THE GROUND.

ENSURE BRACING IS FIXED AS PER AS1684.2010 AND ENGINEERS DETAILS.

BY MIN. 20mm GROUT OR MORTAR. BEARING TO BE MIN. 250mm LONG

MPa UNO AND BE FULLY BEDDED ON 1:0.5:4.5 MORTAR('M4' AS PER AS-3700).

MASONRY SHALL NOT OVERHANG THE LINTEL WIDTH BY MORE THAN 25mm

ALL CROSS WALLS SHALL BE FULLY BONDED FOR THEIR FULL HEIGHT.

HIGH-BUILD EPOXY MICACEOUS IRON OXIDE (TWO-PACK) TO AS3750 14

CONSTRUCTION IN LAYERS OF 300MM TO 7 BLOWS OF PSP TEST.

PERPENDS, BUILD IN CAVITY TIES AT 4c-400 CRS AND STAGGER

CONCRETE SHALL BE VIBRATED TO INDUSTRY STANDARDS.

RESPECTS TO NCC AND APPROPRIATE AUSTRALIAN STANDARD

MESH TO BE PLACED WITH MAIN WIRES VERTICAL.

LIMESTONE BLOCKS TO BE NON- FRIABLE AND OF HIGH-DENSITY TYPE.

DISTRIBUTION REINFORCEMENT TO HAVE 500 LAP SPLICES AS REQUIRED

LINTELS TO BE SUITABLY PROPPED DURING BRICK LAYING TO MAINTAIN LEVEL.

T-LINTELS TO BE CENTRAL TO WALL WITH MIN. 20mm MORTAR TO TOE OF LINTEL.

BRICK WORK AND BRICK TIES TO CONFORM WITH AS4773.1, NCC P2.1, AND AS3700

CLASS 1; IN CONTACT WITH GROUND. BITUMINOUS COATING BELOW GROUND LEVEL IS NEEDED.

STICK ROOF BEAMS SUCH AS RIDGE BEAMS, UNDERPURLINS AND HIP RAFTERS TO BE SUPPORTED

• BATTENS MUST BE ADEQUATELY SUPPORTED BY TIMBER BLOCKS OR STEEL ANGLE TO PREVENT

ALL NON-LOAD BEARING WALLS TO BE KEPT CLEAR OF THE UNDERSIDE OF SLABS AND BEAMS BY

WHERE CONCRETE BEARS ON LOAD BEARING MASONRY OR BRICKWORK, TROWEL SMOOTH AND

BEDDING UNDER A BEARING OF A STEEL BEAM ON MASONRY AND CONCRETE SHALL BE PROVIDED

LOAD BEARING BRICKS SHALL HAVE A MINIMUM CHARACTERISTIC COMPRESSIVE STRENGTH OF 12

AT LEAST TWO BED JOINTS OF WALLS, JUST ABOVE AND JUST BELOW OPENINGS, SHALL BE

LINTELS TO HAVE MIN. 150mm END BEARING UNO. OR BE FIXED TO STEEL COLUMNS WITH 8PL

ALL BUILT-IN COMPONENTS OF MASONRY CONSTRUCTION INCLUDING WALL TIES. MASONRY

ANCHORS, CONNECTORS, BRICK STRAPS, ETC SHALL BE STAINLESS STEEL GRADE AS1449/316 OR

AFTER FABRICATION, ALL LINTEL, T-LINTELS AND SHELF ANGLES SHALL HAVE DUPLEX COATING

OF 50 MICRO MILLIMETER MIN (TWO-PACK) TO AS3750.13, PLUS 200 MICRO MILLIMETER MIN OF

ALL CORES IN MASONRY HOLLOW BLOCK WORK BELOW GROUND LEVEL MUST BE FILLED WITH

DO NOT BUILD OVER OR ADJACENT TO ANY WATER AUTHORITY SEWERS WITHOUT WATER

BACKFILL TO BE PLACED AND COMPACTED AFTER AT LEAST ONE WEEK OF THE RETAINING WALL

NO SURCHARGE CLOSER THAN RETAINING WALL HEIGHT IS ALLOWED ON THE BACKFILL UNLESS.

BLOCKS TO BE FULLY JOINTED WITH M4 AND 1:1:6 (CEMENT : LIME : SAND) MORTAR, 20mm THICK MIN.

PROP RETAINING WALLS DURING BACKFILLING AND COMPACTING. LEAVE PROPS IN UNTIL ADJACENT

USE STANDARD Ø3.15 MASONRY TIES BETWEEN EACH LEAF AT 500C/C HORIZONTALLY IN EACH

CLADDING TO BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURERS DETAILS FOR THE

ALL STRUCTURAL MATERIAL AND ELEMENTS OF THIS CONSTRUCTION SHALL COMPLY IN ALL

IT IS BUILDER'S RESPONSIBILITY TO READ AND UNDERSTAND PROJECT DOCUMENTS SPECIALLY

WE DO NOT ACCEPT ANY RESPONSIBILITY FOR PERFORMANCE OF STRUCTURAL ELEMENTS OR

CONNECTIONS NOT NOTED IN THESE ENGINEERING DRAWINGS. CLIENT/ BUILDER SHALL ASK FOR

THESE DRAWINGS AND SPECIFICATIONS AND REPORT DISCREPANCIES TO THE ENGINEER PRIOR TO

12 MPa MINIMUM CRUSHING STRENGTH BRICKWORK IN M4 MORTAR WITH FULL BED JOINTS AND

MINIMUM FOUNDATION COMPACTION TO BE 7 BLOWS/ 300mm FOR A DEPTH OF 750mm

LIGHT VEHICLE SURCHARGING, HAND COMPACTORS ARE TO BE USED IN THIS AREA.

CAVITY CONCRETE SHALL BE POURED IN 1m MAX. LIFTS A MINIMUM OF 3 DAYS APART.

CONSISTING OF GALVANIZED COATING OF 600g/m2 TO AS4680 AND NON-INHIBITIVE EPOXY PRIMER

REINFORCED WITH 2-L6 STAINLESS STEEL, EXTENDED 600mm PAST THE OPENING.

FLAT A 5 MINIMUM LAYER OF MORTAR AND SEPARATE THE CONCRETE THEREFROM WITH TWO

7

1.

3.

- 4. STEEL BEAMS TO HAVE FULLY WELDED STIFFENERS AT BEARING POSITIONS. STIFFENERS THICKNESS TO BE THE SAME AS THE WEB THICKNESS.
- 5. STEEL BEAM FLANGES TO BE CONTINUOUSLY SUPPORTED BY JOISTS, RAFTERS, TRUSSES OR STIFFENERS. OTHERWISE REFER TO THE ENGINEER.
- ALL WELDS TO BE IN ACCORDANCE WITH AS 1554 AND AS 4100 UNLESS NOTED OTHERWISE. ALL WELDS TO BE CATEGORY SP. ALL BUTT WELDS TO BE FULL PENETRATION CONTINUOUS. ELECTRODES TO BE CLASSIFICATION E48XX.
- 7. REFER TO AISC 'STANDARDISED STRUCTURAL CONNECTIONS' FOR DESIGNATION AND DETAILS OF CONNECTIONS. BOLT TYPE AND TIGHTENING PROCEDURE ARE DESIGNATED:
- ALL BOLTS TO BE GRADE 8.8/S UNO. ALL BOLTS, SCREWS, NUTS AND WASHERS TO BE HOT DIP GALVANISED HDG900 TO AS4680 (125MICRO MILLIMETER OF THICKNESS).
- 9. MINIMUM CONNECTION TO BE A 10mm CLEAT AND 2-M16 UNO
- 10. ALL NATURAL CAMBERS IN STEELWORK SHALL BE UPWARDS.
- 11. AREAS OF DAMAGED CORROSION PROTECTION THAT REQUIRE REPAIR ON SITE SHALL BE MECHANICALLY CLEANED WITH A POWER WIRE BRUSH TO AS 1627.2. THEN, REINSTATE THE PROTECTIVE COATING, DUREBILD STE OR EQUIVALENT, PER AS3750.1 AND MANUFACTURER'S SPEC
- 12. PENETRATION IN FLANGE OR WEB OF STEEL MEMBERS IS NOT ALLOWED UNLESS APPROVED BY ENGINEER
- 13. ALL STEEL WORK TO BE TREATED AS BELOW.
- INTERNAL: CLASS 2.5 GRIT BLASTED & COATED WITH TWO LAYERS OF INORGANIC ZINC SILICATE PRIMER, NOT LESS THAN 65 MICRON EACH
- EXTERNAL; HOT DIP GALVANISED AFTER FABRICATION (HDG900, 125MICOMILIMETER TO AS4680)
- BELOW FFL; 400 MICRON COAT OF COAL TAR EPOXY IN ADDITION TO ABOVE

 COMPONENTS TO BE CAST IN CONCRETE SHALL BE HOT DIP GALVANISED AFTER FABRICATION
- (HDG900, 125MICOMILMETER TO AS4680).
- 13. WHETHER OR NOT DETAILED ON DRAWINGS, PROVIDE CLEATS, BRACKETS AND DRILL HOLES TO COMPLETE THE STRUCTURE TO THE APPROVAL OF THE ENGINEER.THIS INCLUDES ARCHITECTURAL FIXINGS NOT SHOWN ON THE STRUCTURAL DRAWINGS.
- 14. STEEL BEAM FLANGES ARE ASSUMED TO BE CONTINUOUSLY SUPPORTED BY FLOOR JOISTS.
- 15. ENDS OF TUBULAR MEMBERS SHALL BE SEALED WITH A 6MM THICK PLATE AND CONTINUOUS FILLET WELD.
- 16. ALL WORKMANSHIP AND MATERIALS OF COLD FORMED SECTIONS SHALL BE IN ACCORDANCE WITH AS 4600
- 17. HOLES SHALL NOT BE MADE THROUGH THE BOTTOM FLANGE OF PURLINS FOR THE SUPPORT OF HOOK BOLTS OR BOLTS OR CEILING SUSPENSION SYSTEMS. ALL NECESSARY HOLES SHALL BE MADE THROUGH THE CENTRAL THIRD OF THE WEB.

TIMBER FRAMING

TIMBER TREATMENT

- 1. ALL FRAMING TO CONFORM WITH AS1684-2010
- U.O.N. ALL TIMBER SHALL HAVE A MINIMUM STRESS GRADE OF F8 OR MGP10. ALL FIXING COMPONENTS SUCH AS CLEATS, SCREWS, BOLTS, NUTS, WASHERS, ETC SHALL BE HOT DIPPED GALVANISED (HDG900, 125MICOMILIMETER TO AS4680).
- BOTH ENDS OF M10 BOLTS SHALL HAVE 50X50X3 (min) WASHERS AND BOTH ENDS OF M12 BOLTS SHALL HAVE 65X65X5(min) WASHERS UNO.
- 4. ALL WALLS TO BE LATERALLY RESTRAINED AT TOP AND BOTTOM.
- 5. FOR CONTINUOUSLY RUNNING MEMBERS, MINIMUM BEARING SUPPORTS ARE 50mm AND 100mm AT END AND INTERNAL SUPPORTS RESPECTIVELY.
- 6. BRACING AS PER SECTIONS 8 AND 9 OF AS1684-2010
- 7. MEMBERS WITH D/B>4 SHOULD BE BLOCKED AT SUPPORTS AND MIDSPAN.
- 8. DOUBLE/TRIPLE PROFILES TO BE FULLY CONNECTED IN CONSISTENT WITH AS 1684 & SUPPLIER SPECIFICATION.
- FOR BOLTED CONNECTIONS GENERALLY THE FOLLOWING DIMENSIONS SHALL APPLY U.O.N. END DISTANCE AND SPACING PARALLEL WITH GRAIN = 4 x D EDGE DISTANCE AND SPACING PERPENDICULAR TO GRAIN = 5 x D
 - EDGE DISTANCE AND SPACING PERPENDICULAR TO GRA WHERE 'D' IS DIAMETER OF THE BOLT USED.

FITMENTS OF TIMBER MEMBERS ARE AS BELOW UNO

- 1. RAFTERS/PURLINS AT ALL INTERSECTIONS AND JOISTS ON WALL PLATES/BEAMS VIA DOUBLE PRYDA MULTICRIP.
- 2. JOISTS, BLOCKING BETWEEN JOISTS AND ROOF BEAMS IN-PLANE CONNECTIONS VIA SCREWS AND PRYDA FRAMING BRACKETS (FB45180 OR FB45 220) TO MANUFACTURER'S SPECIFICATIONS.
- BEAMS/DOUBLE JOISTS ON TIMBER WALLS TO SIT ON DS/TS AND FIT VIA TWO PRYDA STRAPS RAPPED ROUND; FITMENT: 6X3.15x35 GALV. NAILS EACH END OF EACH STRAP.
- 4. ALL WALLS ON TIMBER STRUCTURES SHALL SIT ON BEARERS/DOUBLE JOISTS (DJ). FITMENT; AS SHOWN ON TIE DOWN DETAILS.
- ALL TIMBER COLUMNS ON TIMBER STRUCTURES SHALL SIT ON BEARERS/DOUBLE JOISTS (DJ), FITMENT; TWO PRYDA STRAPS RAPPED ROUND; AND 6X3.15x35 GALV. NAILS EACH END OF EACH STRAP.
- 6. TO SUIT WET AREA SET DOWN, INSTALL BEARERS AT LOWER HEIGHT

PINE BASED PRODUCTS (PINE, LVL, I-JOIST) :

H2; IN ENCLOSED AND ABOVE GROUND LOCATIONS

H3; IN EXPOSED LOCATIONS, BUT NOT IN CONTACT WITH THE GROUND

H5: IN CONTACT WITH GROUND, BITUMINOUS COATING BELOW GROUND IS NEEDED

- 7. BEARERS/DOUBLE JOISTS IN-PLANE CONNECTIONS VIA PRYDA SPLIT HANGER AND SCREWS TO MANUFACTURER SPECIFICATION.
- 8. TRUSS ENGINEERING AND TIE DOWN, AND TRUSS ROOF BRACING TO THE TRUSS SUPPLIER'S SPEC AND DETAILS.

COMPLEMENTARY DRAWINGS IF IT IS NEEDED.

- DO NOT OBTAIN DIMENSIONS BY SCALING FROM THE DRAWINGS. ALL DIMENSIONS ARE IN MILLIMETRES AND ALL LEVELS IN METRES UNO.
- ROOF IS NOT TO CARRY ANY ADDITIONAL LOAD SUCH AS HOT WATER SYSTEM. CONSULT ENGINEER IF REQUIRED.
- FLOOR ADDITIONAL LOADING (MPOSED LOAD) IS TO BE LESS THAN 1.5KN/M2. CONSULT ENGINEER IF REQUIRED.
- IT ASSUMED THIS SPECIFICATION IS BEING UTILIZED BY PERSONS WITH A SOUND KNOWLEDGE OF GENERAL CONSTRUCTION AND THE DOWN PRINCIPLES. OTHERWISE, CONSULT WITH THE ENGINEER FOR ASSISTANCE.
- 8. BUILDER TO INFORM CLIENT TO PROVIDE PROTECTION COATING TO ANY EXPOSED TIMBER WITH PAINT OR OTHER PROTECTIVE COATING TO PREVENT DETERIORATION.
- 9. THESE DRAWING AND SPECIFICATIONS ARE SOLELY FOR THE INTENDED RECIPIENT AND FOR THE PURPOSES STATED. THE DRAWING AND SPECIFICATIONS SHOULD NOT BE REPRODUCED IN WHOLE OR PART WITHOUT AGREEMENT OF THIS ENGINEER.
- 10. SELECTION OF COMPACTION METHODS SHALL BE BUILDERS RESPONSIBILITY. DO NOT USE COMPACTION METHODS THAT WILL CAUSE DAMAGE TO ADJACENT STRUCTURES.
- 11. BUILDER TO ADVISE CLIENT NOT TO PLANT TREES OR SHRUBS WITHIN 2.5M OR A DISTANCE EQUAL TO THE ANTICIPATED MAXIMUM HEIGHT OF THE TREES TO THE BUILDING. (WHICHEVER IS MORE).
- 12. BUILDER TO INFORM THE CLIENT OF NECESSITY TO MAINTAIN DRAINS IN GOOD WORKING ORDER.
- 13. BUILDER TO DRAIN ROOF AND SURFACE WATER 1200mm (Min.) AWAY FROM FOUNDATION AREA DURING AND AFTER CONSTRUCTION UNO.
- 14. ALL NOTES IN THIS SHEET SHALL BE APPLIED IN MATERIAL PURCHASING AND CONSTRUCTION PHASES, UNLESS, IN DRAWINGS, NOTED OTHERWISE (UNO).
- 15. CLIENT/BUILDER SHALL ENQUIRE ABOUT FIRE RATING (BAL) OF THIS DEVELOPMENT AND INFORM ENGINEER IF FIRE RATING IS EQUAL OR BIGGER THAN 29.

0	31.10.16	ISSUED FOR CONSTRUCTION
В	31.10.16	ISSUED FOR REVIEW NOT CONSTRUCTION
A	27.10.16	ISSUED FOR REVIEW NOT CONSTRUCTION
Rev.	DATE	DESCRIPTION

CLIENT:

DRAWING TITLE: STRUCTURAL ENGINEERING JOB NUMBER: GR218 SHEET- 0 OF 12 DRAWN:RS CHECKED:R.S. SCALE:Shown JOHN REZA SHIRAZ NER MIEAUSt 4051420 GRIEng Consulting www.GRIEng.com Ph. 08 6262 8238 1Wexford St. Subiaco ABN 65 424 055 048